

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 8 E.	I-7 I-6
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9/20 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- I-7 Sec. Cor. 14-15-22-23, set by Wm. Ives, D.S. 1849.  
Bearings were:  
Cedar 8" S20°W 22 Lks. and Y. Birch 9" N66°E 29 Links
- I-6 4 Corner bet. Secs. 14-15, set by Wm. Ives, D.S. 1849.  
Bearings were:  
Beech 6" N25° 20 Lks. and Lynn 5" S55°E 11 links.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- I-7 Found a hemlock (green) and a dead maple stub, blazed on four sides, many years ago. Found evidence of old Cedars on ground but could not identify any as original.
- I-6 Corner placed midway and on line bet. two Sec. Cors. Found on evidence of original corner.  
Corner lies 35.0' West of N.-S. road.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
Placed 1" pipe with 4" aluminium cap at both corners.

- I-7 New Bearings:  
9" Soft Maple N69°E 19.3' and 10" Soft Maple N6°W 41.8' and  
10" Hard Maple S69°W 37.2'  
Corner lies 80' N. of a log road and in an old skid trail.
- I-6 New Bearings:  
14" Y. Birch S60°E 20.4 and 14" Hemlock S50°E 58.0'

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 12/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 887 (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_