

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. S., R. <u>8</u> E. W.	K-1, K-2, K-3
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1/18 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- K-1 Sec. Cor. 1-2-35-36, on North Township Boundary, set by Wm. A. Burt, June 26, 1840. Bearings were: Spruce 4" N20°E 19 lks. and Spruce 4" N12°E 14 lks.
 - K-2 $\frac{1}{4}$ Cor. bet. Secs; 1-2, set by Wm. Ives, D.S., Aug. 1849. Bearings were: Aspen 11" S34°W 28 lks. and Spruce 6" N35°E 10 lks.
 - K-3 Sec. Cor., 1-2-11-12, set by Wm. Ives, D.S. in 1849. Bearings were: Cedar 10" N85°E 11 lks. and Spruce 9" N85°E 15 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- K-1 Corner re-established in center of N.-S. road and in line with old stakes to East and West. Found original corner, one mile to East.
 - K-2 $\frac{1}{4}$ Corner re-established, in center of N.-S. road and by single proportionate measure, between two Sec. Cors.
 - K-3 Sec. Cor. re-witnessed, as recorded by M.S.H.D. Found railroad spike in road, at corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- K-1 Corner re-witnessed. Monument will be placed when County road is filled and improved.
New Bearings: 6" Cedar S61°W 73.0' ; 8" Cedar N68°W 82.6' and 6" Cedar S77°E 96.1'
 - K-2 Corner re-witnessed.
New Bearings: 6" Cedar N47°W 70.9' ; 10" Cedar N87°E 71.3' and 12" Cedar S70°E 71.6'
 - K-3 Corner re-witnessed.
New Bearings: 5" Cedar S61°E 65.4' ; 7" Cedar N52°W 62.5' and 8" Cedar S71°W 63.1'

SIGNED BY Billy D. Buckler DATE 3/5/73
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____