

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

LUCY Co

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 45 N. R. 8 W.	1-9
2. PROPERTY CONTROLLING IN SECTION.....	T. .... N. S. R. .... E. W.	-----
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. .... N. S. R. .... E. W.	-----
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 8/21 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 Sec. Cor. 22-23-26-27, set by Butler Ives, D.S. in 1849.  
 Bearings were:  
     Sugar 7" S43°E 28 Links  
     Spruce 13" N27°W 37 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Found original evidence at corner, but did find very old blazed lines to North, South, East and West.  
 Found trouble Line Trees; 14" hemlock, 4.78 chs. West, and a 25" hemlock, 8.79 chs. East.  
 Position checks well with original corner, 1/2 mile to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Placed 1" pipe with 4" aluminium cap at corner.  
 New Bearings:  
     8" W. Ash      South 30.4'  
     9" Soft Maple N57°E 70.9'  
     22" Hard Maple N52°W 49.8'

SIGNED BY Billy D. Buckler DATE 9/13/72  
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 3007 (SEAL)  
 FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)