

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co Two Corners

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. R. <u>8</u> W.	I-8 I-10
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on I-8, 8/21-I-10, 9/89-72 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
I-8 Original $\frac{1}{4}$ Cor. bet. Secs. 22-23, set by Butler Ives, D.S. 1849.
Bearings were:

Fir 10" S45°W 14 Links
Hemlock 14" N30°E 17 Links

I-10 Original $\frac{1}{4}$ Cor. bet. Secs. 26-27, set by Butler Ives, D.S. 1849.
Bearings were:

Y. Birch 9" N85°E 19 Links
Sugar 12" N80°W 14 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
I-8 Found remains of lower face with scribe marks on a down hemlock.
Distance South to swamp (1 chain) checks well.

I-10 Corner re-established midway and on line between two Sec. Cors.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at both corners.

I-8 New Bearings:
15" Soft Maple N80°W 26.2'
22" Y. Birch S13°W 22.9'

I-10 New Bearings:
28" W. Pine N78°E 104.8'
8" Soft Maple S38°W 48.8'

SIGNED BY Billy D. Buckler DATE 9/13/74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8827 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____