

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Loc. Corners

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 8 E.	G-11 I-11
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on G-11, 7/17-1-11, 9/89-72, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- G-11 Sec. Cor. 27-28-33-34, set originally by William Ives, D.S. in 1849.
 Bearings were:
 Hemlock 10" N75°E 34 Links
 Hemlock 9" N83°W 25 Links
- I-11 Sec. Cor. 26-27-34-35, set originally by William Ives, D.S. in 1849.
 Bearings were:
 Beech 10" N24°E 41 Links
 Cedar 6" S20°W 33 Links
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- G-11 Corner replaced from the NE Bearing tree; a Hemlock still green with face chopped out, years ago. Found numerous blazes, both North and South of corner. Corner lies 4.0' East of a woods trail.
- I-11 Corner re-established midway and on a straight line bet. Corners; one mile South and one mile North. Corner lies in the NE Corner of a large burned opening
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
 Placed 1" pipe with 4" aluminium cap at both corners.
- G-11 New Bearings:
 9" Cedar S80°E 3.7'
 14" hemlock N76°W 17.8'
- I-11 New Bearings:
 6" Soft Maple N57°W 36.2'
 8" Soft Maple N23°W 50.8'

SIGNED BY: Billy D. Buckler DATE: 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 6887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)