

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Luce Co. Tie Corners

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. Sec. 8 R. 8	K-6 G-12
2. PROPERTY CONTROLLING IN SECTION	T. S. R.	E. W.
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R.	E. W.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9/11 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-6  $\frac{1}{4}$  Corner bet. Secs. 13-14, originally set by Butler Ives, D.S. 1849.  
 Bearings were:  
     Fir 7" S57°E 10 Links  
     Beech 8" N15°W 23 Links
- G-12  $\frac{1}{4}$  Corner bet. Secs. 33-34, originally set by Butler Ives, D.S. 1849.  
 Bearings were:  
     Fir 6" S34°E 15 Links  
     Sugar 12" N40°W 23 Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-6 Replaced  $\frac{1}{4}$  Corner, 475.2' North of an original W. Pine Line Tree (Record = W. Pine 30" at 32.80 chs. from South). Found a wood Post in place, set by unknown persons.
- G-12 Re-established  $\frac{1}{4}$  Corner midway and on line bet. two Sec. Cors. No evidence of original Corner, which lies in a large, burnt opening..

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Placed 1" pipe with 4" aluminium cap at both corners.

- K-6 New Bearings:  
     14" Hemlock S83°E 82.4'  
     10" Hemlock S43°W 9.3'
- G-12 New Bearings:  
     No Witnesses Available.

SIGNED BY Billy D. Buckler DATE 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 3827 (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)