

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Two Corners

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|---------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 45 N. R. 8 E. W. | I-12 K-9 |
| 2. PROPERTY CONTROLLING IN SECTION | T. S. R. E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 1-12, 9/8-K-9, 9/11/1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- I-12 Sec. Cor. bet. Secs. 34-35, set by Butler Ives, D.S. in 1849.
 bearings were:
 Sugar 15" N49°E 17 Links
 Beech 5" S74°W 22 Links
- K-9 Sec. Cor. 23-24-25-26, set by Butler Ives, D.S. in 1849.
 bearings were:
 Fir 10" S52°E 15 Links
 Y. Birch 6" N46°W 10 Links
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- I-12 re-established; Cor. midway on line bet. two Sec. Cors.
 Found no evidence of original corner.
- K-9 Replaced Sec. Corner at record distance (2.85 chs) East of an original Cedar line tree. Found a large Soft Maple, blazed on four sides, SW, 5.0'.
 Found blazes to North, South and West.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- I-12 Placed 1" pipe with 4" aluminium cap at corner.
 New Bearings:
 10" W. Pine N30°W 38.8'
 10" Soft Maple S35°W 22.8'
- K-9 Placed 1" pipe with 4" aluminium cap at corner.
 New Bearings:
 15" Soft Maple N25°E 24.9'
 13" Hemlock S74°W 23.6'

SIGNED BY: Billy D. Buckler DATE: 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 25-7 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)