

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

Two Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>45</u> N. S. R. <u>8</u> ^{SE} W.	K-7 K-8
2. PROPERTY CONTROLLING IN SECTION.....	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 9/12 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- K-7 Sec. Cor. 13-14-23-24, originally set by William Ives, D.S. 1849.
Bearings were:
Sugar 12" N73°W 10 LKS
Fir 10" N80°E 10 LKS
 - K-8 1/4 Corner bets Secs 23-24, originally set by William Ives, D.S. 1849.
Bearings were:
Fir 6" N58°W 23 Links
Fir 5" N57°E 25 Links

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- K-7 Sec. Cor. re-established by single proportionate measure bet. Corners; 1/2 mile North and one mile South.
Found no evidence of original corner.
 - K-8 1/4 Cor. re-established midway end on line bet two Sec. Cors.
Found no evidence of original Corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-7 Placed 1" pipe with 4" aluminium cap at corner.
New Bearings:
7" Soft Maple S43°W 31.5'
12" Y. Birch N62°W 38.4'
 - K-8 Placed 1" pipe with 4" aluminium cap at corner.
New Bearings:
8" Cedar N51°W 22.0'
26" Cedar S87 1/2°E 25.9'

SIGNED BY Billy D. Buckler DATE 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 3587 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____