

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970  
Luce Co. 1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <sup>N.</sup> <del>S.</del> , R. <u>8</u> <sup>W.</sup> <del>E.</del>	E-12
2. PROPERTY CONTROL- ING IN SECTION _____	, T. _____, <sup>N.</sup> <del>S.</del> , R. _____, <sup>E.</sup> <del>W.</del>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, <sup>N.</sup> <del>S.</del> , R. _____, <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-24, 19 77, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**E-12** Quarter Corner between Sec's, 32-33, set by Wm Ives, D.S. in 1849.  
Bearings were; Cedar 8, S62°E, 15 lks. and Cedar 10, N63°W, 12 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


**E-12** Restored corner midway and on line between two Section Corners. Cedars in vicinity but none could be identified as witnesses. Corner falls North of a swamp edge as record indicate.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**E-12** Placed 1" pipe with 4" aluminium cap at corner.  
New Bearings: 8" B. Spruce, N12°W, 8.4' and 8" B. Spruce, S42°E, 8.3'.

SIGNED BY Billy D. Buckler DATE 9-14-78  
**Billy D. Buckler**

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_