

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. 2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. <u>X</u> , R. <u>8</u> W.	C-11 B-12
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-25 & 12-1, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-11** Section Corner 29-30-31-32, set by Wm Ives, D.S. in 1849.
 Bearings were: Hemlock 8", N62°E, 13 lks. and Hemlock 8", S20°W, 8 lks.
- B-12** Center Corner of Section 31, T45N R8W.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11** Replaced corner from two original witnesses; a stump with lower face, notch and scribe marks, N62°E, 13 lks. and a stump S20°W, 8 lks., badly deteriorated but with some scribe marks remaining.
- B-12** Corner set at intersection of lines connecting opposite quarter corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at both corners.
- C-11** New Bearings: 10" S. Maple, S65°W, 18.0' and 9" S. Maple, S51°E, 27.5' and 8" S. Maple, N56°E, 29.1'.
 Corner lies on top of a ridge and 12' SE. of an old trail.
- B-12** Bearings: 7" Spruce, N61°E, 35.6' and 9" Aspen, N67°W, 21.8' and 6" Aspen, S11°W, 12.2'.

SIGNED BY Billy D. Buckler DATE 2-9-79
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____