

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. 2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. <u>X</u> , R. <u>8</u> W.	C-12 B-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-27 & 12-1, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners set by Wm Ives, D.S. in 1849.

- C-12 Quarter Corner between Sections 31-32, bearings were: Hemlock 7", S68°E, 20 lks. and Maple 5", N30°W, 13 lks.
- B-11 Quarter Corner between Sections 30-31, bearings were: Spruce 4", S54°E, 11 lks. and Willow 4", N10°W, 06 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-12 Restored corner between two Section corners, found no evidence of original corner.
- B-11 Restored corner by single prop. measure between two Section corners.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at both corners.

- C-12 New Bearings: 6" Cedar, S67°E, 48.1' and 8" Cedar, N60°E, 48.6' and 6" B. Spruce, N82°W, 11.6'.

- B-11 New Bearings: 4" Cedar, N57°E, 37.5' and 5" Cedar, N28°W, 30.2'.

SIGNED BY Billy D. Buckler DATE 2-9-79
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____