

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce

2 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <input checked="" type="checkbox"/> E. R. <u>8</u> W. <input checked="" type="checkbox"/>	A-11, A-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-30, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
Corners set by Wm A. Burt, D.S. in 1840. Bearings were:

A-11 Sec. Cor. bet. Sec's. 30-31, T45N R8W and Sec's. 25-36, T45N R9W.  
1840 Bearings: Cedar 8", S66°W, 10 lks. & Cedar 14", N11°W, 31 lks.  
1849 Bearings: Cedar 11", N42°E, 39 lks. & Cedar 10", S26°E, 52 lks.

A-12 Quarter Corner bet. Sec. 31, T45N R8W and Sec. 36, T45N R9W.  
Sugar 14", S66°W, 18 lks. & Hemlock 14", N72°W, 19 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-11 Placed corner in Center of N-S road and in line with old road to West. Found corner 1/2 mile West and one mile East to confirm this position.

A-12 Found Iron, in Center of Road, set by B. Jones, R.L.S. Found Iron Pipes set for witnesses, bearing N45°W, 45.0' and S45°E, 45.0'.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Buried 36" "T" Iron in Road at corner. New Bearings:

6" Cedar (NET), N88°E, 44.5' & 9" Cedar, (S25 NBT), N62°W, 53.1' & 6" Cedar, (S36 NBT), S77°W, 57.5'. & Fence Corner, S59°W, 37.7' & U.S.G.S. Bench Mark Monument, TT 19S, S55°W, 37.8'.  
Corner is 7.0' North of present culvert.

A-12 Recording corner as set by B. Jones. No new witnesses noted.

SIGNED BY Billy D. Buckler DATE 7-31-80  
Billy D. Buckler  
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET