

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 45N R 8W	E13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 12 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


A. Description of original monument and accessories and/or subsequent restoration:
 (E13) Standard corner common to Sections 32-33. Reestablished by single proportionate measurement in 1960 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap. 6" B.Cherry N40W 52.5 links, 6" B.Cherry N44E 53 links. Closing corner for Sections 4 & 5 T44N-R08W lies 27 links east of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E13) Recovered the 1960 monument, as described, a 1" ID iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the remaining Cherry NE NBT. The other Cherry NBT is gone. Also found a 1" iron pipe with Michigan DNR cap (closing corner Sec. 4-5 T44N-R08W) East, 17.82' Left the standard corner monument in place and marked new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E13) Found 1" pipe with 4" brass cap.
 Blazed, scribed, and set measuring nails
 in the following:
 8" Cherry N46E 35.55' "S33"
 5" Maple S35W 7.9' "S5 NBT"
 14" Cherry N42W 35.05' "S32 NBT"
 Distances are to nail with tag.
 Bearings are magnetic.
 Found MDNR monument East, 17.82'
 Placed squared and scribed cedar post
 adjacent to the corner.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/3/00

For the Michigan Department of Natural Resources - Forest Management Division