

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                          |               |
|---------------------------------------|--------------------------|---------------|
| <u>Luce</u><br>(County)               | Located In:              | Corner Code # |
| 1. Public Land Survey                 | T <u>45N</u> R <u>8W</u> | <u>L7</u>     |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                          |               |
| 5. Private Claims                     |                          |               |

Register of Deeds Stamp & File Number

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

Jun 19 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**


(L7) Quarter corner common to Sections 13 and 24. 1849: Established by Wm. Ives: East random between Sections 13 & 24. 80.00 intersected 60 links South of Post. West corrected S89 deg. 35'W ...40.00 Set quarter section post. Fir 8 N30W 20, Spruce 5 S70E 8...80.00 Corner. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L7) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between M7 (remonumented in 1960 by Billy D. Buckler and recorded by Buckler in 1961 and Neff in 1968), and reestablished K7 (monumented in 1972 by Billy D. Buckler). I observed the mean true bearing and distance of this line to be S89 deg. 29'03"W, 5289.78' (80.15 ch).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L7) Set a 1"IDx36" I.pipe with a 4" alum. MDNR cap, appropriately stamped. Blazed, scribed, and set meas. nails in:  
 10" Spruce S45W 6.6' "1/4S NBT"  
 14" Balsam S36E 11.55' do  
 6" Maple N84W 3.9' do  
 6" Maple S68E 38.7' do  
 Placed a squared cedar post adjacent. Bearings are magnetic. Distances are horizontal and to nail with tag 33986.



Signed by Stephan J. Szyszkoski Date 10/16/03  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities