

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45N</u> R <u>8W</u>	<u>I6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15	●	14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I6) Quarter corner common to Sections 14-15. 1849: Established by Wm. Ives: N10'W between Sections 14 & 15 ...40.00 Set qr Sect. post. Beech 6 N25W 20, Lynn 5 S55E 11 ...80.00 Section corner. 1972: The corner was reestablished midway between two section corners by Billy D. Buckler. Set 1" pipe with 4" aluminum cap. 14" Y.Birch S60E 20.4, 14" Hemlock S50W 58.0' (ref. LCRC L1 P120 Luce County Records).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I6) Recovered the 1972 monument in good condition and at record bearing and distance from the 1972 witnesses, the hemlock in good condition with overgrown blazes and the Y.Birch a stump. I determined that the monument's position is N19W 3.07' from the proportionate position between I5 and I7 as now monumented and accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I6) Found 1" ID I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 16" Hemlock S60W 58.7' "1/4S N8T" *
 4" Maple N87W 7.65' do
 10" Hemlock N51E 15.5' do
 9" Hemlock S17E 23.35' do
 Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/16/03

For the Michigan Department of Natural Resources, Office of Land and Facilities