

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>45N</u> R <u>8W</u>	<u>K9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 25 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. 1849: Established by Wm. Ives: North between Sections 25 & 26...80.00 Set post. Fir 10 S52E 15, Y.Birch 6 N46W 10. West corrected btwn Sections 23 & 26: 2.85 Cedar 10. 1972: The corner was remonumented 2.85 ch. east of the remains of the original Cedar Line Tree by Billy D. Buckler. Set 1" iron pipe with 4" aluminum cap. 15" Soft Maple N25E 24.9', 13" Hemlock S74W 23.6' (ref. LCRC LI P88 Luce County Records).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) The original post and accessories were not recovered. Recovered the 1972 monument in good condition and at record bearing and distance from the 1972 witnesses, both in good condition. The scribing is visible on the Maple. The blazes are overgrown on the Hemlock. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Found 1" I.pipe with 4" aluminum MDNR cap. Blazed, scribed, and set measuring nails in:
 18" Maple N28E 25.4' (old marks plain)
 16" Hemlock S77W 23.95' "S26"
 19" Maple N24W 16.1' "S23 NBT"
 18" Hemlock S10E 35.85' "S25 NBT"
 Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 10/16/03
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities