

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>45N</u> R <u>8W</u>	<u>M6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M6) Quarter corner common to Section 13 T45N-R08W and 18 T45N-R07W. 1960: Billy D. Buckler, RLS reestablished the corner midway and on line between Section corners. Set 1" I.pipe with 4" Brass Cap. 12" Cedar S07E 34.5 links, 8" Cedar S45W 28 links (ref. LCRC 423A, Luce County Records). 1968: Harold Neff, MDOT, records: Found 1/4 corner common to Sec's. 13-18. 1/4 Corner being 4" square post. 3" Balsam 27.00 S80W, 4" Balsam 14.56 S75E, 12" Spruce 14.49 N07W. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M6) Found the 1960 monument, a 1" ID Iron pipe with 4" brass MI Dept. of Conservation cap, in good condition, and at record bearing and distance from the stump of the remaining 1960 witness Cedar SW and from the standing dead Spruce described in the 1968 record. The other NBTs were not recovered. An old squared and scribed cedar post was found adjacent. I suppose that Mr. Neff may have mistaken this post for the corner monument proper and made his record accordingly. The 1960 monument was recovered 2649.70' north of monumented M7 and 2645.49' south of M5 as reestablished and monumented Oct. 13, 2003. I found M6 to be 0.23' west of a straight line between M5 and M7 and accept it as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M6) Found a 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 14" Cedar N66W 25.5' "1/4S NBT"
 10" Cedar S83W 36.55' do
 12" Cedar S64W 35.95' do
 3" W.Birch N25E 13.56' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/16/03

For the Michigan Department of Natural Resources, Office of Land and Facilities