

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45N</u> R <u>8W</u>	<u>M7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

(M7) Corner common to Sections 13-24 T45N-R08W and 18-19 T45N-R07W. 1840: Established by Wm. A. Burt: "Set post corner of Sections 13 & 24 Pine 30 S36W 24, Hemlock 12 N44E 5". Witnesses made by Deputy Surveyors during subdivisions of T45NR08W and T45NR07W: W.Pine 30 N60E 5, Fir 6 S38E 16. 1960: The corner was remonumented from a probable OBT W.Pine stump N60E 05 links by Billy D. Buckler. Set 1" pipe with 4" brass cap. 14" Cedar N75W 24 links, 13" Cedar N45E 70 links, 7" Balsam S15W 17 links (ref. LCRC 861A Luce County Records). 1968: Harold Neff, MDOT, reports that he found "Iron pipe and brass cap" and he made the following witnesses: 8" Spruce S50E 22.71', 8" Spruce S65W 24.92', 4" Spruce N25W 19.33'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M7) Recovered the 1960 monument laying on the ground surface, having been extracted by persons unknown. Reinstalled the recovered monument at record bearing and distance from the following NBTs: the 1960 Cedar NW in good condition, the 1968 Spruces, all now dead: SE found standing with measuring nail, SW now a stump, NW now a stump. Made new witnesses as described below. The remaining witnesses of record were not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M7) Set 1" IDx36" I.pipe with 4" brass MI Dept of Conservation cap. Blazed, scribed, and set measuring nails in:
 20" Cedar N77W 16.35 "S13 NBT" *
 4" Y.Birch N60E 12.45' "S18 NBT"
 9" Spruce S49E 23.2' "S19 NBT"
 6" Maple S22W 33.15' "S24 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes the 1960 NBT



Signed by Stephan J. Szyszkoski Date 10/16/03
 Surveyor's Michigan License No. 33986