

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce (County)	Located In:	Corner Code #	
1. Public Land Survey	T 45N R 8W	K8	
	T R		
	T R		
	S T		
2. Property Controlling in Section	S 14 T 45N R 8W	6	
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims
 6 Jun 18 2003
 K8 Jun 25 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(K8) Quarter corner common to Sections 23 and 24. 1972: The corner was reestablished by Billy D. Buckler midway and on line between Section corners. Set 1" pipe with 4" aluminum cap. 8" Cedar N51W 22.0', 26" Cedar S87 1/2E 25.9' (ref. LCRC L1 P87 Luce County Records).
 (6-Sec. 14) Northeast 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K8) Recovered the 1972 monument in good condition and at record bearing and distance from the remains of the 1972 witnesses. The Cedar NM is now a stump, that SE is a windthrow. Left the monument in place and made new witnesses as described below.
 (6-Sec. 14) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K8) Found 1" ID I.pipe with 4" aluminum MDNR cap. Blazed, scribed, and set measuring nails in: 4" Maple N74E 20.75' "1/4S NBT" 6" Cedar N13E 8.55' do 4" Maple N31W 14.5' do 12" Cedar S12W 47.0' do Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(6) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" Maple S51E 2.7' "NE1/16 BT" 16" Maple N62E 30.5' do 10" Maple S38W 15.5' do 12" Maple N78W 27.8' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/16/03

For the Michigan Department of Natural Resources, Office of Land and Facilities