

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luca</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S 24 T 45N R 8W	8	
	S 24 T 45N R 8W	1	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims  
 1 Jun 19 2003  
 8 Jun 23 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 24) West 1/16 corner, Section 24. Not established in the original survey.
- (1-Sec. 24) West 1/16 corner between Sections 13 & 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 24) Established the corner midway and on a straight line between Quarter corner 1323.89' west and Center of Section 1323.89' east.
- (1-Sec. 24) Established the corner midway and on a line of mean true bearing between Section corner 1322.44' west and Quarter corner 1322.44' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (8) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set measuring nails in:<br>14" Balsam S50W 9.8' "W1/16 BT"<br>12" Maple N83W 19.35' do<br>8" Cedar S77E 14.55' do<br>5" Maple N12W 24.3' do | (1) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set measuring nails in:<br>12" Spruce N87E 8.05' "W1/16 BT"<br>6" Maple S21E 5.1' do<br>6" Maple West 15.25' do<br>6" Maple N48W 22.05' do |
| Set squared cedar post adjacent.<br>Bearings are magnetic. Distances are to nail with tag.  | Cedar post adjacent. Bearings are magnetic. Dist. to nail with tag.  |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/16/03

For the Michigan Department of Natural Resources, Office of Land and Facilities