

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Luce

|                                    |                          |               |
|------------------------------------|--------------------------|---------------|
| (County)                           | Located In:              | Corner Code # |
| 1. Public Land Survey              | T <u>45N</u> R <u>8W</u> | <u>L5</u>     |
|                                    | T _____ R _____          | _____         |
|                                    | T _____ R _____          | _____         |
|                                    | T _____ R _____          | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____         |
|                                    | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                    | S _____ T _____ R _____  | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 09 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    | ● |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:  
 Quarter corner common to Sections 12-13. 1849: Established by Wm Ives, Deputy Surveyor: West corrected between Sections 12 and 13...39.78 Set Qr. Section post. Cedar 8 S85E 21, Cedar 12 S40W 10...79.56 Corner. 1969: Michigan State Highway Dept. R.O.W. Survey File No. 48042-Sur-1, sheet No. 12 notes: 1/4 cor. Monument Box. 12" Balsam N35W 77.48', 6" Cedar N18E 73.04', wood post S50W 68.03', 1.90' Right (south) of Sta. 448+52.84. 1995: Field notes dated Feb 2 1995 by Lawrence Weinreis, PS, Michigan Dept. of Transportation state: Found 1" O.D. pipe with pipe cap on top. Falls +/- 1.5' South of existing C/L M-28. Found the cedar bearing tree. Found a nail with M.S.H.D. ref. tag in side. Chopped out and replaced with nail with M.D.O.T. ref. tag. Added 3 witnesses. Corner in monument box. 10" Cedar N25W 83.02', 10" Cedar N18E 72.76', 6" Cedar S40W 85.21', 8" Cedar of triple S10E 81.29'. Nail with MDOT ref tag in side of objects. Trees blazed. Distances E.D.M.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 The original post and accessories were not recovered. Found and accepted a 1" O.D. iron water pipe capped with a threaded cap in a monument box +/- 1.5' south of the existing centerline of Highway M-28. The 1995 MDOT witnesses are still in place and are in substantial accord with the 1995 record. My measurements to Section corners east and west suggest strongly that this monument was intended to mark the reestablished proportionate GLO position on a straight line and midway between X5 and M5. In 2003, corner M5 was reestablished 5.85' north of the monument that presumably controlled the prior reestablishment of L5. As a result, L5 is now 3.03' south of a line between X5 and the reestablished M5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" O.D. iron pipe with pipe cap in monument box 1.5' South of existing C/L Highway M-28.  
 10" Cedar N18E 72.76'  
 10" Cedar N32W 83.02'  
 6" Cedar S37W 85.21'  
 8" Cedar of triple S12E 81.29'  
 Bearings are magnetic. Distances are to a found nail with MDOT ref. tag in the side of the tree.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/8/04