

#32

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located In:	Corner Code ##
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ 19 T ___ 45N R ___ 9W	___ 10
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on November 01, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration.

(10-Sec. 19) South 1/16 corner between section 19 T45N-R9W and section 24 T45N-R10W. Corner established in 1976 by Billy D. Buckler RLS as follows: Placed midway between 1/4 corner to North and Section corner to South. Placed 1" pipe with 4" aluminum cap. Witnesses: 8" R. Pine S68W 12.1', 6" R. Pine S52E 9.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(10-Sec. 19) Found Buckler's monument at record bearing and distance from the 1976 BTs. Marked two additional witnesses trees and placed measuring nails with tags in all 4 trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.



(10) Found 1" pipe with 4" MCHR cap Blared, scribed, and set measuring nails in the following BTs:
12" R. Pine S68W 12.1
10" R. Pine S52E 9.65'
8" R. Pine N86W 11.5' "S1/16 BT"
6" R. Pine S25W 12.0' "S1/16 BT"
Bearings magnetic.

Signed by Stephan J. Szyszkoski Date 1-27-94
Surveyor's Michigan License No 33986