

25

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 8W 65
T R
T R
T R

2. Property Controlling
in Section

S 10 T 45N R 8W 15
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 04 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							•	•					
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(65) Corner common to Sections 9-10-15-16. Corner re-monumented in 1951 by Dean C. DeLaMater, RLS: "This corner pointed out to me by J. Halbach, District Forester, of Newberry. One original B.T. still in place, in fair condition. Placed 1" pipe with 4" brass cap. 8" Cedar N11E 16 links, 10" Cedar S80E 39 links, 6" Cedar S05W 21 links".
(15-Sec. 10) West 1/16 corner between Sections 10-15. Corner established in 1974 by Billy D. Buckler, RLS midway between Section and Quarter corners. Placed 1" pipe with 4" aluminum cap and marked 12" W. Birch S10E 14.1', 12" W. Birch S86E 10.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(65) Found and accepted DeLaMater's monument, now a 1" pipe with the cap rusted off, at record bearing and distance from the 1951 witnesses, now all dead. Removed the 1951 monument, and placed at it's position, a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
(15-Sec. 10) Found Buckler's monument in good condition, and at record bearing and distance from his 1978 witnesses, now both dead stubs. Left the monument in place and marked four new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(65) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following new bearing trees: 6" Cedar S68E 2.5' "S15 NBT" 8" Cedar N26E 7.2' "S10 NBT" 8" Cedar S64W 14.45' "S16 NBT" 8" Cedar W11W 19.7' "S9 NBT"	(15) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following new bearing trees: 4" Cedar S80W 24.95' 6" Spruce N78W 27.75' 5" Spruce N42E 30.1' 3" Cedar S30W 32.55' Centerline of M-28 is North 110'. Placed a cedar post adjacent. Placed a location poster approx. 80' north. Bearings are magnetic.
Placed 4" squared and scribed cedar post adjacent. Centerline of M-28 is 138' North. Location poster is North 107'. Bearings magnetic.	

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2-1-96



For the Michigan Department of Natural Resources - Forest Management Division