

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Luce

Located In: Corner Code #

1. Public Land Survey

T 45N R 8W C13  
T 45N R 8W A13

2. Property Controlling  
In Section

S T R  
S T R

3. Miscellaneous  
Property in Sec.

S T R  
S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A13 Sep 18 1995

C13 Sep 20 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

A. Description of original monument and accessories and/or subsequent restoration:

(C13) Corner common to Sections 31-32. Corner reestablished in 1969 by Billy D. Buckler, RLS from the closing corner common to Sections 5-6 T44N-R8W. Buckler placed 1" pipe with 4" aluminum cap and marked the following: 13" Cedar N10W 9.5', 11" Soft Maple M29E 46.4'

(A13) Corner common to Townships 44N-45N, Ranges 8W-9W. Corner re-witnessed and recorded in 1969 by Billy D. Buckler, RLS: 2" iron pipe in 8" concrete monument. Found two 2" iron pipes, placed as witnesses, bearing N45W 45.0' and S45E 45.0'. Fence corner 33.0' West of corner. 8" Hard Maple N01W 18.8', 8" Hard Maple S60W 20.0'. Monument lies in line with roads to north and east.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(C13) Recovered Buckler's monument as described, in good condition, and at record bearing and distance from his 1969 witnesses. Re-marked the top blaze and placed a measuring nail in the 1969 Cedar. This corner is being recorded in order to update the accessories.

(A13) Recovered the 2" pipe monument as described, in good condition, and at record bearing and distance from the 1969 witness H. Maple S60W. The other witness had been cut. Left the pipe in place and marked three new witness trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(C13) Found 1" pipe with 4" MONR cap. Blazed and scribed the following bearing trees:

16" Cedar N10W 9.2' "S31"  
7" Y. Birch S46W 7.65' "S6 NBT"  
4" Alder S64E 4.0' "S6 NBT"

East'ly 24.40' 1" pipe with 4" aluminum cap at Section corner 5-6 T44N-R8W.

Set location poster 350' north of corner in field. Bearings are magnetic.

(A13) Found 2" pipe in 8" concrete base. Blazed, scribed, and set measuring nails in the following:

10" H. Maple S60W 20.3' "S1"  
(Above is 1969 rec. bearing)  
3" Aspen N55W 5.2' "S36 NBT"

4" Aspen N35E 4.5' "S31 NBT"  
5" H. Maple S25W 16.9' "S1 NBT"

Bearings magnetic. Placed a location poster 85' east at a N-S trail.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11-29-95

For the Michigan Department of Natural Resources - Forest Management Division