

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co. 5 Corners.

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> ^{N.} _X , R. <u>9</u> ^{E.} _X	3-Sec.10, 4-Sec.10
2. PROPERTY CONTROLLING IN SECTION	<u>10</u> , T. <u>45</u> ^{N.} _X , R. <u>9</u> ^{E.} _X	8-Sec.10, 11-Sec.10
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____, R. _____	12-Sec.10
4. LOT NO. _____	, RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5/17, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 3-Sec.10 North 1/16 Corner on West side of Section 10.
- 4-Sec.10 North-West 1/16 Corner of Section 10.
- 8-Sec.10 West 1/16 Corner of Section 10.
- 11-Sec.10 South-West 1/16 Corner of Section 10.
- 12-Sec.10 South 1/16 Corner of Section 10.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 3-Sec.10 Placed corner on sec. line bet. Sec. Cor. North and computed position of $\frac{1}{4}$ Cor. South.
- 4-Sec.10 Placed corner at center of North-West quarter section.
- 8-Sec.10 Placed corner midway bet. computed center corner and computed quarter corner on West side section.
- 11-Sec.10 Placed corner at center of the South-West quarter section.
- 12-Sec.10 Placed corner midway bet. center corner North and $\frac{1}{4}$ Corner South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners.
- 3-Sec.10 Bearings: 8" Maple, N22°E, 57.9' and 10" Spruce, S74°W, 64.8'
 - 4-Sec.10 Bearings: 12" Hemlock, N62°E, 13.1' and 10" Cedar, N52°W, 39.7'
 - 8-Sec.10 Bearings: 10" Maple, S47°W, 15.7' and 8" Maple, N35°E, 40.6'
 - 11-Sec.10 Bearings: 6" Maple, S63°E, 27.5' and 4" Balsam, N24°W, 9.9'
 - 12-Sec.10 Bearings: 10" Cedar, N11°W, 22.5' and 6" Cedar, S54°W, 10.6'

SIGNED BY Billy D. Buckler
 Billy D. Buckler

DATE 1/17/77



SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____