

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Luce Co.

Four Corners.

| FOR CORNERS OF--:                            | LOCATED IN--:  | CORNER CODE NUMBER          |
|--|--|-----------------------------|
| 1. PUBLIC LAND SURVEY_____                   | T. <u>45</u> <sup>N.</sup> <del>X</del> , R. <u>9</u> <sup>W.</sup> <del>X</del>   | <u>10-Sec.19, 12-Sec.19</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>19</u> | , T. <u>45</u> <sup>N.</sup> <del>X</del> , R. <u>9</u> <sup>W.</sup> <del>X</del> | <u>11-Sec.19, 13-Sec.19</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____   | , T. _____ <sup>N.</sup> <del>X</del> , R. _____ <sup>W.</sup> <del>X</del>        | _____                       |
| 4. LOT NO. _____, RECORDED PLAT _____        |  |                             |
| 5. PRIVATE CLAIMS _____                      |  |                             |

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11/10, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 10-Sec.19 South 1/16 Corner, on Westside of Section 19.
- 11-Sec.19 South-West 1/16 Corner of Section 19,
- 12-Sec.19 South 1/16 Corner of Section 19.
- 13-Sec.19 South-East 1/16 Corner of Section 19.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 10-Sec.19 Corner placed midway bet.  $\frac{1}{4}$  Cor. to North and Sec. Cor. to South.
- 11-Sec.19 Placed corner at center of SouthWest quarter section.
- 12-Sec.19 Placed corner midway bet. Center Corner and South  $\frac{1}{4}$  cor.
- 13-Sec.19 Placed corner at center of South-East quarter section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners.
- 10-Sec.19 Bearings: 8" R. Pine, S68°W, 12.1' and 6" R. Pine, S52°E, 9.4'
- 11-Sec.19 Bearings: 12" J. Pine, S61°E, 68.0' and 6" R. Pine, S32°W, 55.2'
- 12-Sec.19 Bearings: 10" R. Pine, S42°E, 38.8' and 8" R. Pine, S18°W, 22.9'
- 13-Sec.19 Bearings: 10" S. Maple, N59°W, 7.6' and 10" Ironwood, S40°W, 17.5'

Note: 12-Sec.19, Corner lies 22' North of Pine Plantation.

SIGNED BY Billy D. Buckler DATE 1/17/77  
Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_