

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~44~~⁴⁵ NR 9 W

Luce & Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 3-4-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	16" Hard Maple	N 28° E	34½ links
	"S 34 NBT"		
	8" Hard Maple	N 40° W	44 links
	"S 33 NBT"		
	9" Hard Maple	S 51° E	54 links
	"S 3 NBT"		

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one yellow birch B.T. (green) in excellent condition, bearing S 57° E 19 links.

Steel fence post in place.

Corner lies in E-W fence line.

Found by Jim Halbach, District Forester.

Yellow birch B.T. N 12° E 36 links cut recently by logger.

SURVEYORS SEAL

SIGNED Willy D. Buckles DATE 6/11/57
REGISTERED LAND SURVEYOR