

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Corner bet. Secs. 28-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6-31-69

WITNESSES TO CORNER..... 5" Soft Maple (½S NBT) N51°W 18.8'



5" Soft Maple (½S NBT) S62°W 30.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on line bet. two Sec. Cors and at record distance (2649.3') from corner ½ mile east. Position checks with swamp edges and stream to east and west. The ½ mile to west is longer (68.4'). than record.

Corner lies 60' south of road and on east side of a skid trail.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 1-26-70