

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 6-23-69

WITNESSES TO CORNER..... 14" Soft Maple (S29 NBT) N31°W 16.3'



5" Soft Maple (S32 NBT) S37°17.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two hemlock stumps bearing S50°W, 18 lks and N78°E, 27 lks. Both stumps down, badly rotted, in very poor condition. Found some old scars but nothing definite. Found old Y. Birch windfall near corner with several old axe blazes. Position fits with swamp edges, 4.00 chs. north, 3.78 chs. east and to south. Found 1" iron pipe 7.5' east and 19.5' south of corner. Apparently placed recently by unknown surveyor.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1-26-70
REGISTERED LAND SURVEYOR