

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ corner bet. Secs. 19-30

CORNER MONUMENT ¼ Corner bet. Secs. 19-30

DATE MONUMENT PLACED AND WITNESSED 6-31-69

WITNESSES TO CORNER..... 6" Red Pine (¼S NBT) S71°W 8.7'



7" Jack Pine (¼S NBT) North 9.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on line and by single proportionate measure bet. Cors.  
½ mile to east and west.  
Found no evidence of original corner.  
Corner lies 40' north of the south edge of Jack Pine plantation.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1226-70  
REGISTERED LAND SURVEYOR