

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

	Located In:	Corner Code #
1. Public Land Survey	T 45N R 9W T 45N R 10W	A-6 M-6
2. Property Controlling In Section	S ___ T ___ R ___ S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	___

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 89 469

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Keith R. Waters, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 (T45N, R9W) 1/4 Corner Common to Sec. 18, T45N, R9W & Sec. 13, T45N, R10W

Original ties to post:
Ironwood 6, S29°E 21 links
Ironwood 4, N46°W 20 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 (T45N, R9W)

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner. Re-established corner on line between established Section corners 1/2 mile north and south at the intersection of the extension of remains of an old fence line to the west. North-south position is within 1.5 feet of a split between said Sections corners north and south. Also found remains of a north-south right-of-way fence approximately 33 feet west of corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 (T45N, R9W)

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap approximately 1.5 feet east of east edge of pavement on County Road 403 at remains of a fence line to the west. Witnesses:

- 4" Sugar Maple, N57°E 14.33'
- 9" Red Pine, S59°W 66.29'
- 10" Red Pine, S76°W 61.62'
- Power Pole (ML2-28-11), WEST 44.68'

Note: Distances are to a nail and tag in the side of witness object. Pines are blazed and painted. Bearings are compass bearings corrected for declination. Maple is not blazed.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Keith R. Waters Date 12-20-93
Surveyor's Michigan License No. 33142