

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>9W</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Filed 12-22 A.D., 19 93

At 10:00 o'clock A. M.

File No. 93 474

Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5 1/4 Corner Common to Sections 7 & 18, T45N, R9W

Original ties to post:
Beech 6, N53°W 23 23 links
Sugar 14, S31°E 35 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner or its accessories. Re-established corner by single proportionate measurement between section corners 2643.22' east and 2620.76' west. Position checks well with found concrete monuments on the west 1/16 line of Section 18, which I found earlier this year as part of a survey in the NW 1/4 of the NW 1/4 of said Section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5
Corner is a 1/2" rebar with 3 1/2" aluminum Luce County cap 2 feet north of centerline of Highway M-28. Witnesses:

- 15" Scotch Pine, N17°W 61.12'
- 4" Scotch Pine, N37°E 51.80'
- 11" Scotch Pine, S48°E 74.16'
- 8" Scotch Pine, S16°E 62.73'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142