

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in LUCE

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 9W	C-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 477

Kathy S. Mahan
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Keith R. Waters in a field survey on September 93

I, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2 1/4 Corner Common to Sections 5 & 6, T45N, R9W

Original ties to post:
Sugar 9, N45°E 04 links
Sugar 5, S48°W 13 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner. Distance between section corners 1/2 mile north and 1/2 mile south is within 4.5 feet of original G.L.O. distance. Re-established corner by single proportionate measurement between Section corners 2579.69 feet north and 2637.72 feet south. Corner falls approximately 33 feet east of remains of a north-south fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap approximately 33 feet east of remains of a north-south fence line. Witnesses:

- 5" Sugar Maple, S59°E 25.60'
- 8" Sugar Maple, S24°E 21.22'
- 6" Sugar Maple, S22°W 30.66'
- 8" Sugar Maple, S78°W 28.64'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142