

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 45N R 9W C-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Filed 12-22 A.D., 1993

At 10:00 o'clock A. M.

File No. 99 475

*Kathy S. Mahan*  
 Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-6 1/4 Corner Common to Sections 17 & 18, T45N, R9W

Original ties to post:  
 Yellow Birch 10, S32°E 34 links  
 Beech 14, N23°W 31 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner or its accessories. Re-established corner by single proportionate measurement between section corners 2640.26' north and 2640.26' south. Corner falls in the approximate centerline of a north-south dirt road (County Road 401) at the approximate centerline of a dirt road to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap in the approximate centerline of north-south dirt road (County Road 401). Witnesses:

- 8" Cherry, N32°E 58.18'
- 10" Cherry, S76°E 38.82'
- 7" Cherry, S16°E 102.71'
- 10" Aspen, S50°W 112.64'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	●	17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

