

1993

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>9W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Filed 12-22 A.D.; 19 93

At 10:00 o'clock A.M.

File No. pg 472

Walter S. Mahan
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

D-5 1/4 Corner Common to Sections 8 & 17, T45N, R9W

Original ties to post:
Sugar 16, N35°W 10 links
Beech 6, S40°E 08 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner or its accessories. Re-established corner on line between section corners 2668.40 feet east and 2626.30 feet west on the centerline of County Roads 408 to the north and 399 to the south. East-west position fits with several north-south fence lines on small parcels to the east on the south side of Highway M-28. East-west position also fits with a north-south fence line at the west 1/16 line of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5

Corner is a 1/2" rebar with 3/4" aluminum Luce County cap 0.7 feet north of the centerline of Highway M-28 at the centerlines of County Roads 408 to the north and 399 to the south. Witnesses:

Power Pole (ML2-51-1), N18°W 85.32'
8" Red Pine, S42°E 117.20'
6" Red Pine, S24°E 93.54'
NE Corner Concrete Block Building,
S48°W 156.32'

Note: Unless noted otherwise, distances are to a nail and tag in the side of witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142

