

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------------------|------------|
| 1. Public Land Survey | T <u>45N</u> R <u>9W</u> | <u>113</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>36</u> T <u>45N</u> R <u>9W</u> | <u>16</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Jul 29 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L13) Quarter corner common to Sec. 36 T45N-R9W Luce Co., and Sec. 1 T44N-R9W Mackinac Co. Corner re-witnessed in 1968 (record dated 3/14/69) by Billy D. Buckler RLS: 2" iron pipe. 9" Twin hard maple N01W 66.2', 14" Elm S20E 59.9' (16-Sec. 36) East 1/16 corner between Section 1 T44N-R09W Mackinac Co. and Section 36 T45N-R09W Luce Co. Rewitnessed in 1968 (record dated 3/14/69) by Billy D. Buckler RLS. Found 2" iron pipe. No witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L13) Recovered a 2" iron pipe in good condition at record bearing and distance from the presumed NBT Maple North, which is only a single tree, with old blazes. The elm was not recovered. Left the monument in place and marked new witnesses as described below. (16-Sec. 36) Found 2" ID iron pipe at edge of plantation. Made rough measurement east and west 1/4 mile to adjacent corners to check position of pipe. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L13) Found 2" ID iron pipe. Blazed, scribed, and set measuring nails in the following:
 18" Maple North 66.2' "1/4S NBT"
 18" Maple S52W 43.2' do
 5" W.Pine S67W 29.2' do
 5" Cherry N55E 55.75' do
 Approx. edge of Red Pine plantation S80E 60'. Bearings are magnetic. Distances are to nail w/tag.

(16) Found 2" iron pipe. Blazed, scribed, and set measuring nails in the following:
 6" Cherry S04E 38.25' "E1/16 BT"
 4" Cherry S48E 47.4' do
 5" Cherry N40E 29.4' do
 4" R.Pine N70E 50.8' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 4/18/00
 Surveyor's Michigan License No. 33986