

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce	Located In:	Corner Code #	
<small>(County)</small>			
<b>1. Public Land Survey</b>	T <u>45N</u> R <u>9W</u>	<u>F11</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
<b>2. Property Controlling in Section</b>	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
<b>3. Miscellaneous Property in Sec.</b>	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 05 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11						●							
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (F11) Quarter corner common to Sections 28-33. Reestablished in 1969 by Billy D. Buckler RLS at record distance (2649.3') from corner 1/2 mile east, on line between section corners, and in accord with record distance to swamp edges and stream to east and west. Buckler states the west 1/2 mile is 68.4' longer than record. 1" pipe with 4" aluminum cap. 5" Soft Maple N51W 18.8', 5" Soft Maple S62W 30.2'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F11) Recovered the 1969 monument in good condition and at record bearing and distance from the 1969 NBTs. The Maple S62W is a 2' high stump. The Maple N51W is in good condition with scribe marks visible. Distance west to Section corner was found 2717.58', in accord with Buckler's record. This corner is being recorded in order to describe new accessories.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F11) Found 1" ID iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in the following:  
 8" Maple N52W 19.15' "1/4S"  
 6" Maple N47E 4.6' "1/4S NBT"  
 14" W. Birch East 17.85' do  
 12" W. Birch S66E 22.45' do  
 Fence post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/28/01

For the Michigan Department of Natural Resources - Forest Management Division