

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>45N</u> R <u>9W</u>	<u>E11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 05 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (E11) Corner common to Sections 28-29-32-33. Established in 1849 by William Ives, DS: North between Sections 32 & 33..80.00 Set post corner of Sections 28-29-32-33. Hemlock 12 S50W 18, Hemlock 12 N78E 27. Perpetuated 6/23/1969 by Billy D. Buckler, RLS (record dated 1/26/70): "This corner replaced from remains of two hemlock stumps bearing S50W 18 links and N78E, 27 links. Both stumps down, badly rotted, in very poor condition. Found some old scars but nothing definite....Position fits with swamp edges...Found 1" iron pipe 7.5' east and 19.5' south of corner". Corner monument 1" pipe with 4" aluminum cap. Witnesses: 14" Soft maple N31W 16.3', 5" Soft Maple S37 [sic] 17.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) Recovered the 1969 monument, a 1" ID iron pipe capped with a 4" dia. cast aluminum State of Michigan tablet, in good condition, appropriately stamped, and at record bearing and distance from the NBT Soft Maple N31W, standing but decayed with no markings visible. The second Soft Maple NBT was found in good condition, now 12" DBH, blazes overgrown, in the SW quadrant, at record bearing and distance. The original BTs are now gone. Accepted the 1969 monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place. The iron pipe noted in the 1969 record is still in place and is not accepted for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

(E11) Found 1" ID iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in:
 12" Maple S38W 17.1' "S32 NBT"
 8" Twin Maple N58W 30.75' "S29 NBT"
 5" Spruce S08E 20.1' "S33 NBT"
 6" Cherry N35E 25.95' "S28 NBT"
 1" iron pipe S17E 20.55'
 A wooden post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/28/01

For the Michigan Department of Natural Resources - Forest Management Division