

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luca</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>9W</u>	E10	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>28</u> T <u>45N</u> R <u>9W</u>	10	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 05 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29	●	28		27		26		25	
11				●								
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (E10) Quarter corner common to Sections 28-29. Corner reestablished in 1969 by Billy D. Buckler RLS: "This corner reestablished midway and on line between two Sec. Cors. Found old wood post lying on ground at corner, but found no original evidence." Buckler placed a 1" ID pipe with 4" aluminum cap. Witnesses: 9" Hard Maple S52W 11.9', 14" Hard Maple North, 31.8' (10-Sec. 28) South 1/16 corner between Sections 28-29. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E10) Recovered the 1969 monument in good condition and at record bearing and distance from the 1969 NBTs, both in good condition. Measured 2627.12' south to Section corner. Accepted the monument and used it to establish the 1/16 corner to the south. Left the monument in place and made new witnesses.
 (10-Sec. 28) Established the corner midway and on a line of mean true bearing between Section corner 1313.55' South and Quarter corner 1313.55' North. Found a 1/2" iron pipe, not of record, South (mag. brg.), 16.0' from the monument, and is not accepted for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E10) Found 1" ID iron pipe with 4" alum. MDNR tablet. Blazed, scribed, and set measuring nails in:	(10) Set 1" ID x 36" iron pipe with 4" dia. alum. MDNR cap. Blazed, scribed, and set measuring nails in:
12" Maple S50W 11.85' "1/4S NBT"	6" Maple N62W 12.15' "S1/16 BT"
16" Maple N03W 32.05' do	10" Maple S35W 7.55' do
12" Maple N74W 7.05' do	5" Maple S70E 11.0' do
12" Cherry S14E 13.5' do	6" Maple N53E 9.3' do

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 8/28/01
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division