

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>09W</u>	<u>E2</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	●	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on Jan. 28, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (E2) Quarter corner common to Sections 4 and 5. 1849 - Established by Wm. Ives, Deputy Surveyor, 40.00 chains north of Section corner E3, 38.72' chains south of Section corner E1, and on the Section line between Section corners E1 and E2. Set post. B.Ash 10 N35W 06 links, Fir 6 S48E 20 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (E2) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the Section line between Section corners 2615.74' south and 2532.04' north, being proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (E2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Cedar N53E 7.25' mrkd "1/4S NBT"
 6" Cedar N63W 5.0' do
 9" Cedar S69W 6.65' do
 8" Cedar S28E 19.9' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 1/30/08

Surveyor's Michigan License No. 33986