

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	S <u>5</u> T <u>45N</u> R <u>09W</u>	<u>1</u>	
2. Property Controlling in Section	S <u>5</u> T <u>45N</u> R <u>09W</u>	<u>3</u>	
	S <u>5</u> T <u>45N</u> R <u>09W</u>	<u>4</u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
4. Lot No. <u> </u> , Recorded Plat <u> </u>			
5. Private Claims			

**Register of Deeds Stamp & File
Number**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	5	4	3	2	1					
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on Jan. 28, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 5) West 1/16 corner between Section 5 T45N-R09W and Section 32 T46N-R09W. Not established in the original survey.

(4-Sec. 5) Northwest 1/16 corner, Section 5. Not established in the original survey.

(3-Sec. 5) North 1/16 corner between Sections 5 and 6. Not established in the original survey. From the corner position, the Government plat gives distances 20.00 chains south to Quarter corner and 19.12 chains north to Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 5) Established the corner midway and on the Township line between Section corner 1319.18' west and Quarter corner 1319.18' east. The center of an E-W logging road is approx. 10' north of the corner position.

(4-Sec. 5) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(3-Sec. 5) Established the corner on the Section line between Quarter corner 1318.94' south and Section corner 1260.91' north, being the position proportionate to the measures given on the original Government plat. From the corner monumented, the center of a N-S trail is 14.5' east and the center of a trail easterly is 5' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 11" Cedar N66W 10.88'; 7" Cedar N52E 32.0'; 6" Cedar S70E 25.5'; 11" Cedar S07E 23.0'; all marked "W1/16 BT". Bearings are magnetic.

(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 6" Maple clump N05W 5.05'; 7" Cedar N80E 50.9'; 6" twin Balsam S80E 11.54'; 7" W.Birch S33W 19.76'; all marked "NW1/16 BT". Bearings are magnetic.

(3) Set 1"IDx36" I.pipe with plastic cap stamped "Mich DNR LS33986", buried flush with the ground. Set measuring nail with MDNR tag in the side of: 14" R.Pine N25W 9.5'; 10" R.Pine S67W 38.2'; 10" Maple clump S39E 58.35'; 10" twin B.Cherry S85E 51.1'; all marked "N1/16 BT". Bearings are magnetic.

Signed by Stephan J. Szyszkoski 1/30/08 Date

Surveyor's Michigan License No. 33986

