

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 45N R 9W	9
	S 19 T 45N R 9W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 13 09/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 19) East 1/16 corner, Section 19. Established by Billy D. Buckler in 1976, midway and on a straight line between Center of Section 1313.8' west and Quarter corner 1313.8' east: Set 1" pipe with 4" MDNR cap. 8" W.Pine S23E 44.2'. Corner lies 330' east of pine plantation corner.

(13-Sec. 19) Southeast 1/16 corner, Section 19. Established by Billy D. Buckler RLS in 1976 at the intersection of straight lines connecting opposite 1/16 corners. Set 1" ID iron pipe with 4" MDNR cap. 10" S.Maple N59W 7.6', 10" Ironwood S40W 17.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 19) The 1976 monument and W.Pine BT were not recovered. Found no evidence of the 1976 position of the corner on the ground. Reestablished the corner midway and on a straight line between Center of Section 1313.90' west and Quarter corner 1313.90' east.

(13-Sec. 19) Found the 1976 monument in good condition. The 1976 witnesses were not recovered. Verified the position of the monument with respect to Center of Section, East 1/16 corner, and East 1/4 corner Sec. 19, and found it to be in accord with the 1976 record. Accepted the corner as a careful and faithful establishment of the position of the corner. Made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" W.Pine N66W 48.83' mrkd "E1/16 BT"
 8" Balsam S14W 58.55' do
 6" Ironwood S60E 82.25' do
 13" Maple N66E 80.32' do
 Bearings are magnetic.

(13) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" Maple N02E 4.85' mrkd "SE1/16 BT"
 17" Maple S27W 23.75' do
 12" Maple S69W 21.47' do
 11" Maple S32E 23.0' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/19/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

