

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
LUCE  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>10W</u>	<u>A10</u>
	T <u>45N</u> R <u>10W</u>	<u>A11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>29</u> T <u>45N</u> R <u>10W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A11 May 26, 1992

A10 May 26, 1992

I, Stephan J. Szyszkoski, in a field survey on 15 May 27, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(A10) 1/4 corner between Sections 30 (T45N-R10) and 25 (T45N-R11W). Corner previously recorded by Billy D. Buckler in 1970 as a wood post placed by single proportionate measure to the original survey, with the following witnesses: 16" Hard Maple (1/4S NBT) S52E 43.3', 6" Hard Maple (1/4S NBT) S75W 40.6'.

(A11) Section corner common to sections 30 and 31 of T45N-R10W, and 25 and 36 of T45N-R11W. Corner previously recorded by Billy D. Buckler in 1970 as a 1" pipe with a 4" aluminum cap set by single proportionate measurement with the following witnesses: 13" Hard Maple (S25 NBT) N65W 25.1', 12" Hard Maple (S36 NBT) S22W 14.2', 14" Soft Maple (S30 NBT) N89E 9.3'.

(15) West 1/16 corner between Section 29 and 32. Corner not established in original survey. Corner established by Eino Sainio as noted on Land Corner Certificate for the South 1/4 corner of Section 29.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A10) Recovered post hole and flagging at corner in accord with Buckler's witnesses. BT S52E is dead. Old blaze is visible but scribing has rotted away. BT S52E is green. Cut out overgrown blaze to reveal scribing and scribed a BH blaze. Placed a Department of Natural Resources monument in the post hole and marked 3 new bearing trees as described below.

(A11) Found and accepted Buckler's monument and accessories as recorded but noted that Buckler's bearing to NBT N85W was found to bear N78W. Placed additional witness tree, scribed Buckler's BT's at BH, and set measuring nails in them. Corner lies on top of a seal N-S ridge about 10' high, 76' south of an E-W 2-track trail.

(15) Found 1/2" rebar with cap 97873 disturbed at corner location. Replaced rebar with a 1" painted iron pipe capped with a 4" cast aluminum MDMR tablet midway and on a straight line between Section corner 1311.58' west and 1/4 corner 1311.58' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(A10) Set a 1"x32" painted iron pipe capped with a 4" cast aluminum MDMR tablet. N20E 10.3' set nail and MDMR tag in N. face 6" maple (1/430 NBT), S64E 7.0' nail and MDMR tag in S. face 7" maple (1/430 NBT), S77W 41.0' nail and tag in E. face 8" maple (Buckler's), N73W 5.1' set nail and MDMR tag in S. face 7" maple (1/425 NBT). Set sq'd 4" balsam post 1' east. Placed location tag N71W 1260' on 5" sq'd maple at trail.

(A11) Found 1" pipe with 4" aluminum MDMR tablet. N08E 29.0' set nail and MDMR tag in W. face 12" maple (S30 NBT), S89E 9.0' set nail and MDMR tag in SW face 10" hard maple (S30 at BH above old blaze), S22W 13.75' set nail and MDMR tag in NW face 12" maple (S36 above old blaze), N78W 25.2' set nail and MDMR tag in S. face 14" maple (S25 above old blaze). North 66' placed location poster at road on squared 9" maple. Placed 4" squared balsam post 1' NE of corner.

(15) Set 1" pipe as described above. Place measuring nails with MDMR tags in the following trees: S54W 35.15' in N face 9" maple (1/16 BT), N72W 11.68' in S face 7" maple (1/16 BT), N13E 35.25' in N face 8" maple (1/16 BT), S71E 29.1' in S face 9" maple (1/16 BT). Corner lies in SW corner of a seal clearing.

Signed by Stephan J. Szyszkoski

Date June 8, 1992

Surveyor's Michigan License No. 33986

