

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 10W	K9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 16 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (K9) Corner common to Sections 23-24-25-26. Corner monumented at the original position in 1952 by Michigan Dept. of Conservation Surveyor Dean C. DeLaMater: "This corner was found by Forestry Division survey crew while making a partial resurvey of this area. Two original 8.I.'s still in place, poor condition. Corner was placed and witnessed June 24, 1952. Description of corner monument: 1" pipe with 4" brass cap, witnesses to corner: 26" W. Pine N32W 114 links, 8" Beech N55E 52 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) Found the 1952 monument as described (a 1" I.D. iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation Forestry Division tablet), in good condition, and at record bearing and distance from the 1952 witnesses. The 26" W. Pine is now a cut and rotting stump with no markings visible. The Beech is now 12" dia. in good condition. The ground-level remains of the original bearing trees noted in the 1952 record were recovered at record bearing and distance. Left the monument in place and marked three new accessories as described below. Corner recovered and rewitnessed by T.Stark, Newberry District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Found 1" pipe with 4" brass cap.
 Blazed, scribed, and set measuring nails
 in the following:

12" Beech N57E 34.2'	"S24 NBT"
6" Maple S14N 2.55'	"S26 NBT"
6" Maple N74N 3.5'	"S23 NBT"
14" Maple S87E 18.45'	"S25 NBT"

Placed a 3" cedar post adjacent.
 Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

Nov. 12, 1997

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division