

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Loc. _____

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 10W	M8
	T 45N R 10W	M7
	T 45N R 10W	M9
2. Property Controlling in Section	S _____ R _____	_____
	S _____ R _____	_____
	S _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ R _____	_____
	S _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, Stephan J. Szyszkoski, in a field survey on November 01, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M8) Quarter corner common to Section 24, T45N-R10W and Section 19, T45N-R9W. Corner previously restored in 1976 by Billy D. Buckler, RLS as follows: Corner restored midway and on line between two section corners. Placed 1" pipe with 4" aluminum cap at corner, New Bearings: 12" R. Pine, S64N 46.3', 8" R. Pine N55W 54.7'. Corner lies 36' west of road.
(M7) Corner common to Sections 13-24, T45N-R10W, and 18-19, T45N-R9W. Corner previously restored in 1969 by Billy D. Buckler RLS as follows: Placed 1 1/4" x 30" iron pipe, buried in N-S road. Witnesses: 11" W. Pine (MBT) S54E 82.7'.
(M9) Corner common to sections 24-25 T45N-R10W, and sections 19-30 T45N-R9W. Corner previously restored in 1969 by Billy D. Buckler RLS from the remains of a probable line tree. Set 1" pipe with 4" brass cap. Witnesses: 8" Jack pine (S19 MBT) N63E 27.9', 7" Red Pine (S25 MBT) S45W 10.6', 7" Red Pine (S24 MBT) N43W 14.8'. Corner lies 45' S of trail road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M8) Found Buckler's monument at record bearing and distance from his two witness trees. Placed measuring nails with tags in them and marked two additional bearing trees, as described below.
(M7) Recovered Buckler's buried iron pipe in a N-S road and at record bearing and distance from the W. Pine MBT. The MBT is dead but still standing. Location postcard and the old fences noted on the 1969 record are gone. Marked 4 new bearing trees as described below.
(M9) Recovered Buckler's monument at record bearing and distance from the J. Pine and R. Pine S45W bearing trees. The other R. Pine MBT has been cut. Remarked the top blaze of the two remaining MBTs, placed measuring nails with tags in them, and marked two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M8) Found 1" pipe with 4" HDNR cap
6" R. Pine N29W 23.5' Nail and tag
P. pole N389 5-35 S45E 83.6' Nail/tag
14" R. Pine S64N 46.6' Nail and tag
10" R. Pine N55W 55.0' Nail and tag
Bearings magnetic.

(M7) Found 1 1/4" iron pipe, buried.
Blazed, scribed, and placed measuring nails with tags in the following new bearing trees:
10" W. Pine S66E 57.5' "S19 MBT"
10" R. Pine S78W 43.95' "S24 MBT"
12" Cherry N73W 31.2' "S13 MBT"
Nail and Tag only in:
P. Pole 1073 SPCS1 S84E 37.0'
Bearings magnetic.

(M9) Found 1" pipe with 4" brass cap.
Blazed, scribed, and set measuring nails with tags in the following:
8" R. Pine N23W 10.0' "S24 MBT"
6" R. Pine S38E 15.45' "S30 MBT"
Placed Nails/tags in the 1969 MBTs:
14" J. Pine N63E 28.0'
12" R. Pine S45W 10.8'
Bearings Magnetic.

Signed by _____



Surveyor's Michigan License No. 33986

Date 1-27-94