

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

LUCE COUNTY <sup>4</sup> Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 <sup>N.</sup> <del>S.</del> , R. 10 <sup>W.</sup> <del>E.</del>	H-II H-I2
2. PROPERTY CONTROLLING IN SECTION 34	T. 45 <sup>N.</sup> <del>S.</del> , R. 10 <sup>W.</sup> <del>E.</del>	4-SEC.34 5-SEC.34
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5/13/76, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-II; Quarter Corner bet. Secs 27-34; set by Wm. Ives, D.S. in 1849. Bearings were; Sugar 14" N61E, 23 Lks. and Sugar 6" S30W, 22 Lks.
- H-I2; Center Corner, Section 34.
- 4-Sec.34; North-East 1/16 Corner, Sec. 34.
- 5-Sec.34; North 1/16 Corner, Sec. 34.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- H-II; Re-established Corner midway bet. two Sec. Cors. Found no evidence of Original Corner.
- H-I2; Placed Corner at intersection of lines connecting opposite 1/4 Cors.
- 4-Sec.34; Placed Corner at center of the North-East Quarter Section.
- 5-Sec.34; Placed Corner midway bet. 1/4 Cor to North and Center Cor. to S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" Pipe with 4" Aluminum Cap. at all Corners.

- H-II; New Bearings:  
10" Hard Maple, S80E, 13.0' and 8" Hard Maple, N21E, 50.6'
- H-I2; New Bearings:  
11" Soft Maple, S70W, 8.1' and 9" Hard Maple, S13E, 7.0'
- 4-SEC.34; New Bearings:  
10" Hard Maple, N31E, 14.7' and 11" Hard Maple, S30E, 25.9'
- 5-SEC.34; New Bearings:  
10" Hard Maple, N13E, 7.5' and 9" Hard Maple, S66E, 11.8'

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 9/22/76  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

