

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 45N N.R. 10-11W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 30-31-25-36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7-31-67

WITNESSES TO CORNER..... 13" Hard Maple (S25 NBT) N85°W 25.1'



12" Hard Maple (S36 NBT) S22°W 14.2'

14" Soft Maple (S30 NBT) N89°E 9.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate measure, bet. corners; one mile south and one mile north.

Corner lies 15' east of an intersection of old roads from south and west; and 1 chain south of an old E.-W. Grade.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 12-2-70
REGISTERED LAND SURVEYOR