

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 44-45N N.R. 10W


Luce and Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 Corner bet. Secs. 1-36

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 12-4-69

WITNESSES TO CORNER..... 8" soft maple (1/2 S NBT) S15°W 24.3'



9" Twin W. Birch (1/2 S NBT) Due East 46.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness, a Hemlock stump, bearing N37°E, 34 links. Found remains of face with calloused overgrowth and notch of bottom blaze. Found no evidence of use at this corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler.
Billy D. Buckler DATE 8-20-70
REGISTERED LAND SURVEYOR