

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 10 E. W.	1-7 1-9
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 2/3 1969, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 Sec. Cor. 14-15-22-23, placed by Wm. Ives, D.S. in 1849.
 Bearings were:
 4" Pine 40" for Sec. Cor. with Sugar 12" S45°E 25 lbs.
- I-9 Sec. C r. 22-23-26-27, set by Wm. Ives, D.S. in 1849.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-7 Corner replaced in site of a 4" S. Pine Stump. Found no other S. Pines in vicinity.
 Distance East to County road and South, one mile to Sec. Cor. checks well.
- I-9 Corner replaced at a hard maple, which had been blazed as a corner by unknown person.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium ca. at both corners.

- I-7 New Bearings:
 8" S. Maple N58°E 16.5' - 9" H. Maple S56°E 12.0' and
 8" H. Maple N67°E 28.0'
- I-9 New Bearings:
 14" S. Maple N41°W 12.4' - 8" H. Maple N43°E 17.6' and
 11" H. Maple S31°E 10.9'

SIGNED BY Billy D. Buckler DATE 3/5/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____