

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Luce Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	N. S. R. E.	
2. PROPERTY CONTROLLING IN SECTION- 36	T. 45 N. R. 10 E.	2,6,7
3. MISCELLANEOUS PROPERTY IN SECTION	N. S. R. E.	
4. LOT NO., RECORDED PLAT.		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-15, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 10-15, 1981, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1 East 1/16 corner between Sec's. 25-36.
  - 2 Northeast 1/16 corner of Sec. 36.
  - 3 North 1/16 corner on East side of sec. 36.
- Corners were not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Corner set midway and on line between section corner to East and 1/4 corner to West.
- 2 Corner set at intersection of North-South and East-West lines from 1/16 corners North, South, East, and computed 1/16 corner to West.
- 3 Corner set midway and on line between section corner to North and 1/4 corner to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

laced 1" pipe with 4" dep't. cap at all three corners. Bearings are:

- 1 8" Cherry, S52°W, 48.2' & 5" R. Pine, N68°W, 53.4' & 18" W. Pine Stump, N32°W, 30.8'.
- 2 12" W. Pine, N76°W, 22.05' & 10" W. Pine, R20°W, 39.4' & 10" S. Pine, S50°E, 33.4'.
- 3 2" Hemlock, S62°E, 60.0' & 10" P. Maple, S16°W, 27.8' & 6" R. Maple, N66°W, 10.0'.

SIGNED BY

*David B. Babbitt*  
David Babbitt

DATE 10-20-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: